

INVOICE

Mini Home Energy Solutions
100 Demo Way, Victoria, BC V8V 1V1
250-555-0147

MES-20260730-003
Issued July 30, 2026
Amount Due: \$13,075.00

BILL TO / INSTALLATION SITE

Jordan Lee
27 Cedar Ridge Road
Port Hardy, BC V0N 2P0

PROJECT DETAILS

Eligibility code: ESP1-DEM00730
Work completed: July 29, 2026
Terms: Due on receipt

HOME-ENERGY UPGRADE WORK COMPLETED

Supply and installation at the address shown above. Amounts are in Canadian dollars.

Qty	Description	Amount
1	Air source heat pump: conversion from wood heating Cold-climate ductless mini-split heat-pump system - supply and installation. TOSOT outdoor unit TW24HXP2A1D0 with indoor high-wall unit TW24HXP2A1DI; primary heating system serving the main living area. AHRI certified reference number: 211177523. Product specs: SEER 24.0, SEER2 24.5, HSPF 11.0, HSPF2 9.5, variable-speed compressor, capacity 20,000 BTU at -5 C.	\$15,850.00
1	Existing wood-heating system decommissioning and removal. Disconnected and removed freestanding wood stove and vent connector; before-and-after photos and WETT visual inspection report supplied.	\$0.00
	CleanBC heat pump rebate credit - Income Level 1	-\$5,000.00
	Customer portion owed for heat pump after CleanBC rebate	\$10,850.00
1	Ventilation upgrade ENERGY STAR certified bathroom exhaust fan - supply and installation. ACIQ model AEP110, ENERGY STAR Unique ID 3629726; 110 CFM nominal airflow and 94.2 CFM at 0.25 in. w.g. Includes insulated ducting to exterior, self-closing backdraft damper, air sealing, and functional test.	\$1,650.00
	CleanBC ventilation rebate credit - Income Level 1, bathroom fan max	-\$300.00
	Customer portion owed for ventilation after CleanBC rebate	\$1,350.00
	Subtotal before rebates	\$17,500.00
	GST (5%)	\$875.00
	Invoice total before rebates	\$18,375.00
	Total CleanBC rebate credits	-\$5,300.00
	Payments / deposits received	\$0.00
	Amount Due / Customer amount due after rebates	\$13,075.00

Supporting documentation supplied

- Matched before-and-after photos showing the wood heating system before removal
and the heat pump installation after completion.
- WETT Level 1 visual inspection report documenting the pre-removal wood appliance.
- TOSOT AHRI product submittal showing AHRI 211177523 and matched heat-pump components.
- ACIQ AEP110 ENERGY STAR label and product specification sheet.

Contractor confirmation: Work completed at the installation address on July 29, 2026.
Equipment was installed and commissioned in accordance with manufacturer instructions
and applicable permits.