

CORRECTED INVOICE - CLAIMS AI TEST014

Invoice #: HP-TEST014-MULTI

Invoice date: 2026-05-15

Contractor: Island Eco Energy Heating and Cooling

Contractor address: 5475 Hardy Bay Road PO Box 5248, Port Hardy, BC V0N 2P0

Customer / participant: Lucy Hemphill

Project site: 9460 Mayors Way, Port Hardy, BC V0N 2P0

Eligibility code: ESP1-Wood5cbd76ab

Line 1 - Air source heat pump with wood/electric backup context

Scope: Supply and install Mitsubishi TW24 single-head mini-split heat pump system.

Outdoor model: TW24HXP2A1DO. Indoor model: TW24HXP2A1DI high wall unit.

AHRI reference: 211177523. Efficiency: 21.0 SEER, 10.5 HSPF, 2.0 ton capacity.

Primary-heating note: installed to serve the main living area as the primary heat pump system.

Backup/existing heat note: previous primary heating source was wood stove plus electric baseboards; no fossil fuel backup heat is installed.

Wood appliance documentation: WETT report attached for removed/decommissioned wood appliance.

Heat pump cost before rebate: \$18,950.00

CleanBC heat pump rebate credit: -\$5,000.00

Line 2 - Attic insulation upgrade

Scope: Blown-in loose fill insulation added to attic over conditioned living space.

Area: 900 square feet of attic floor between conditioned space and unconditioned attic.

Existing insulation: approximately R-20. Added insulation: R-60. Final target: R-80.

Insulation cost before rebate: \$4,850.00

CleanBC insulation rebate credit: -\$1,200.00

CORRECTED INVOICE - CLAIMS AI TEST014 CONTINUED

Invoice #: HP-TEST014-MULTI

Customer / participant: Lucy Hemphill

Project site: 9460 Mayors Way, Port Hardy, BC V0N 2P0

Line 3 - Windows and doors upgrade

Scope: Replace two exterior window rough openings with ENERGY STAR certified windows.

Rough opening count: 2 rough openings replaced.

Installed products: Super Windows Ltd. / Silverline Exterior Solutions 2200 Series.

Window types: one single sliding window and one picture window.

Performance labels: Fenestration energy performance labels attached; CSA A440.2, metric U-factor 1.21 W/m²-K, ER 33 and ER 26.

Manufacturer labels: product manufacturer labels are attached with the fenestration labels.

Windows cost before rebate: \$3,400.00

CleanBC windows rebate credit: -\$200.00 (2 rough openings x \$100.00).

Preapproval note: synthetic test invoice states no City of Vancouver project location; project is Port Hardy, BC.

Invoice totals

Heat pump cost: \$18,950.00

Insulation cost: \$4,850.00

Windows and doors cost: \$3,400.00

Subtotal before rebates: \$27,200.00

Taxes: \$0.00

Total before rebates: \$27,200.00

Total CleanBC rebate credits: -\$6,400.00

Customer amount due after rebates: \$20,800.00

Amount paid by customer to date: \$0.00

Balance due: \$20,800.00

Attached evidence referenced by this corrected invoice: WETT report, insulation before/after photos, fenestration energy labels.