

M

MiniMe Contracting Company

Registered business name: Mini Home Energy Solutions

TAX INVOICE

MME-20260801-184

Issued August 1, 2026 | Due August 31, 2026

CONTRACTOR

MiniMe Contracting Company
Mini Home Energy Solutions
100 Demo Way, Victoria, BC V8V 1V1
service@minimecontracting.ca | 250-949-2248
ESP Registered Contractor No. 00001
GST 81234 5678 RT0001

PARTICIPANT & INSTALLATION SITE

Jordan Lee
27 Cedar Ridge Road
Port Hardy, BC V0N 2P0
Eligibility code: **ESP1-DEMO0730**
Income Level 1

PROJECT SUMMARY

Natural gas conversion

Central ducted heat pump

Northern top-up

Health & safety remediation

Installation completed July 29, 2026. The home's existing natural-gas forced-air furnace was the primary space-heating system, serving all conditioned living areas and more than 50% of the home throughout the heating season to 21 C. The new central ducted heat pump replaces that primary furnace and distributes heat through the same whole-home duct system. No pre-existing or secondary heat pump was present.

QTY	DESCRIPTION	AMOUNT
1	Cold-climate central ducted air-source heat-pump system Supply, installation and commissioning of Bryant variable-speed system: outdoor unit 38MAQB18R--3 , indoor air handler FMC4Z1800AL , and electric auxiliary heat kit. AHRI Certified Reference Number 203380999 references the matched outdoor and indoor components. Qualified Product List category: Central ducted heat pump (Tier 2). SEER 19.0; HSPF Region IV 10.3; rated capacity at -5 C 13,600 BTU/h; cold-climate rated. System serves all conditioned space previously heated by the natural-gas furnace. Electric auxiliary heat is the only backup heat; no fossil-fuel backup remains.	\$19,850.00
1	Existing health and safety issue - attic mould remediation Localized mould and moisture staining at the attic air-handler platform and duct-access route was professionally treated before HVAC installation. Work included containment, HEPA cleaning, approved fungicidal treatment, removal of affected loose debris, drying verification and final visual inspection. This remediation was required to enable safe installation and operation of the eligible heat pump and was confirmed rebate-eligible before work began under reference HSR-2026-4187 . Remediation completed July 22, 2026. Before and after photographic report supplied.	\$840.00
1	Natural-gas primary furnace removal Existing natural-gas forced-air furnace, vent connector and dedicated heating-gas branch removed and disposed of in accordance with permit PH-MECH-26-0714 and applicable local requirements. Removal completed July 24, 2026; final inspection July 29, 2026. Natural gas is no longer used for space heating at the home.	Included
Subtotal		\$20,690.00
GST (5%)		\$1,034.50
Invoice total before rebates		\$21,724.50
CleanBC Income Level 1 central ducted heat-pump rebate credit		-\$16,000.00
CleanBC northern top-up credit - central ducted system; Port Hardy installation is north of and including the District of 100 Mile House and is connected to BC Hydro electric service		-\$3,000.00
CleanBC Income Level 1 health and safety remediation rebate credit		-\$800.00
Total CleanBC rebate credits		-\$19,800.00
Customer amount due after rebates		\$1,924.50

CONTRACTOR CONFIRMATION

Equipment was installed and commissioned at the installation address in accordance with manufacturer instructions, applicable permits and local requirements. The heat-pump rebate, northern top-up and health-and-safety rebate have been itemized and deducted from the participant's amount owing.

Payment: E-transfer to payments@minimecontracting.ca
Reference invoice MME-20260801-184.

Supporting records supplied: remediation photo report, ESP pre-approval, furnace-removal inspection, AHRI product submittal, heat-load/commissioning report and BC Hydro service confirmation.

MiniMe Contracting Company | Invoice MME-20260801-184

Page 1 of 1