



RPR Heating & Air Conditioning Ltd.

Alex Bain
PO Box 106
Hedley, BC V0X1K0

☎ (250) 499-8980
✉ alexandrabain89@gmail.com

INVOICE	#93369-1
INVOICE DATE	Feb 24, 2026
PAYMENT TERMS	Upon receipt
AMOUNT DUE	\$1,985.20

SERVICE ADDRESS

849 Daly Ave
Hedley, BC V0X 1K0

CONTACT US

154 Ellis Street
Penticton, BC V2A 4L5

☎ (250) 492-3677
✉ info@rprheating.com

INVOICE

Materials	qty	unit price	amount
Notes - Supply and Installation	1.0	\$17,450.58	\$17,450.58
1. Bryant Heat Pump with an air handler and a 5 kw back up strip heater 2. Turn the air handler around so it can be serviced and filter can be changed easily 3. 10-years parts warranty 4. 1-year labour warranty; increased to 5-years with enrollment in RPR maintenance plan. 5. RPR will manage product warranty registration on your behalf and will provide a copy of certificate upon completion.			
Bryant Heat Pump - 24,000btu	1.0	\$0.00	\$0.00
Make: Bryant Indoor model: 40MUAQ24XA3 Air handler dimensions: H 45" x W 17.5" x D 21" Outdoor model: 38MURAQ24AB3 SEER2: 17.4 HSPF2: 10 AHRI Ref #: 208447896 Approximate dimensions: H 31.8" x W 37.2" x D 16.1" Sound level: 62 dBA MCA: 20 - Product Bulletin 101-24-25 supersedes nameplate 20.5A Max breaker: 35A Voltage: 208-230V Parts Warranty: 10 years parts Labour Warranty: 1 year Heating Capacity: 24,045btu at -15C Outdoor Unit Location: Back of home (Carport if it will fit) Lineset Length: 20' Lineset Size: 3/8 x 3/4 (10 to 164ft) Fortress Length: 20' Fortress Colour: White Ductwork Fittings Required: Transition / Return drop / Custom platform Filter Size: 20x20x4 Strip Heater Size: 5 kw Thermostat: Ecobee Lite			

Ecobee3 Lite - Installation	1.0	\$0.00	\$0.00
The Ecobee3 Lite thermostat is equipped with the essential features to start saving you up to 23% annually on heating and cooling.			
Features: - 3H/2C Heat Pump or 2H/2C Conventional - Home IQ; Get a monthly savings report and compare your results to other homes in the area. It's like an energy audit at no extra cost. - Smart Recovery; Ecobee3 lite gets to know your home's heating and cooling patterns - Wi-Fi capable - Control from anywhere - 7-day, 5-2, 5-1-1 or non-programmable - ENERGY STAR® Certified - Optional Outdoor temperature sensor - Simple push-button functionality - Filter change reminders - 5-year warranty			
Heat Pump + Air Handler Installation	1.0	\$0.00	\$0.00
PRE-INSTALLATION: - Conduct a pre-installation site visit to address all inquiries and ensure optimal placement of equipment and refrigerant lines. - Obtain necessary permits and document specific details on the invoice.			
INSTALLATION: - Utilize drop sheets to safeguard your flooring during installation. - Responsibly remove and recycle existing natural gas furnace. - Run communication wiring in compliance with electrical codes. - Condensate line routed to either drainage lines, a condensate pump, or a floor drain. - Install required refrigerant lines and covering. - Seal exterior penetrations with mastic or caulking. - Refrigerant lines undergo testing with 600 psi of nitrogen and are held for a minimum of 15 minutes to guarantee material integrity and durability. - Refrigerant lines are evacuated into a vacuum, maintaining a minimum holding pressure of 500 microns for 15 minutes to eliminate any residual moisture in the system. - The work area is meticulously cleaned upon finishing installation. - Air handler and heat pump commissioning is conducted, including refrigerant charging, verification of optimal operating pressures, adjustment of fan speeds for enhanced efficiency, and confirmation of equipment functionality. - Ensure quality workmanship and equipment backed by RPR Heating and Air Conditioning Ltd., a member of the Home Performance Contractor Network, adhering to industry best practices and ongoing quality assurance measures.			
POST-INSTALLATION: - Conduct a walk-through of the new system's operation with installers. - Provide a thorough commissioning checklist for each piece of equipment. - Handle warranty filing and maintain records on your behalf, furnishing a copy for your records. - Schedule a quality assurance visit approximately 1-2 weeks after installation to address any concerns and ensure satisfaction. - Send information regarding RPR maintenance plans.			
Electrical Included	1.0	\$0.00	\$0.00
- Electrical wiring to comply or exceed electrical code CSA Standard C22.1-21. - All required equipment and wiring connections. - Ensure proper voltages are present at equipment. - Exterior penetrations seal with caulking and/or mastic. - Electrical permit pulled and noted on invoice.			
Disconnect: New. Breaker(s): New - 20 amp for condenser and 25 amp for strip heater Surge Suppressor: Yes - To protect the inverter in the event of a power surge or brown out. Wire Length: 20' feet to condenser / 20' to strip heater.			
Rheem - 15amp - Hybrid Heat Pump Water Heater - 40 Gallon	1.0	\$5,460.58	\$5,460.58
Make: Rheem Model: PROPH50 T2 RH375-15 Fuel type: Electric Tank size: 50 USG/42 IMPG Sound Level: 49 dBA Max Breaker: 15A Voltage: 240V Watts: 300 Unit dimensions: H 61.75" x W 22.25" Parts Warranty: 10-years Labour warranty: 1-years increased to 5-years with with yearly maintenance contract - see terms & conditions.			
Outlet Venting Length: 10' Included			
WHAT YOU'LL GET: - Removal and recycle of existing natural gas hot water tank			

- Installation of required venting if applicable
- Wi-Fi Enabled to track your energy usage
- Hot water tank installed
- Connect water to new unit
- Re-connect existing electrical supply unless upgrade required and included in estimate
- Commissioning of hot water tank
- Quality workmanship & equipment backed by RPR Heating and Air Conditioning Ltd.; as a member of the Home Performance Contractor Network, we provide installations that meet or exceed all industry standard best practices, and are subject to ongoing quality assurance measures

Installation Requirements:

Expansion tank
Vacuum breaker

Customers are responsible for making sure there is clear access from the entry of the home to the hot water tank location. Any items or doors that need to be removed in order to accommodate the install are the responsibility of the customer. If RPR is required to remove doors or items that the customer has not removed, We will take no responsibility for any damage or replacement cost of these items. If any finishing work is required we can provide a carpenter at an additional cost.

Multi-Item Install Discount	1.0	-\$1,500.00	-\$1,500.00
-----------------------------	-----	-------------	-------------

Installed with Equipment - Panasonic Bath Fan - Pick-A-Flow	1.0	\$1,650.36	\$1,650.36
---	-----	------------	------------

Make: Panasonic
Model: FV-0511VQ1
CFM: 50-80-110
Warranty: 5-years parts
Sones: 0.3 Sound Rating
Dimensions: H 8.5" x W 13" x D 13"

Ducting Length:

WHAT YOU'LL GET:

- Removal and recycle of existing bath fan if one is present.
- Connect required ducting and attach to termination.
- Exterior penetrations sealed with either mastic or caulking.
- Vapor boot to be used if bath fan is mounted in un conditioned space.

ELECTRICAL - Permits - Installation Electrical Permit	1.0	\$0.00	\$0.00
---	-----	--------	--------

Contractor Name: RPR Heating and Air Conditioning Ltd.
License Number: 205241
Installation Permit Number: EL-2035077-2026

Heat pump subtotal	\$17,450.58
Hybrid hot water heater subtotal	\$5,460.58
Bath fan subtotal	\$1,650.36
Multi-unit discount	(\$1,500.00)
Job Subtotal	\$23,061.52
5% GST	\$1,153.08
Job Total	\$24,214.60

CleanBC Energy Savings Eligibility Code ESP1-NatGasd74fd035

Heat pump rebate	(\$16,000.00)
Hybrid hot water heater rebate	(\$3,500.00)
Bath fan rebate	(\$1,567.84)
Customer Portion	\$3,146.76

Payment History

Jan 23	Fri 9:36am	Credit Card	\$1,161.56
--------	------------	-------------	------------

Thank you for choosing RPR Heating & Air Conditioning Ltd.

Invoices are due upon receipt. For information regarding late payments, please refer to our Terms & Conditions link below.

A 50% deposit is required on all approved estimates over \$1,000.

By accepting this estimate and submitting payment, you agree to our terms.

We accept payment by cash, credit, debit, cheque, or e-transfer to payments@rprheating.com.

Cancellations must be made with at least 24 hours' notice. A \$50 fee applies to late cancellations. Additional travel charges may apply if a technician is already en route or on-site.

Gas Contractor #: LGA0205242

Electrical Contractor #: LEL0205241

WCB #: 201507991

See our [Terms & Conditions](#)